

04-10-03

2151
#10
BT

PTO/SB/21 (03-03)

Approved for use through 04/30/2003. OMB 0651-0031

U.S. Patent and Trademark Office: U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

TRANSMITTAL FORM (to be used for all correspondence after initial filing)		Application Number	10/039,565
		Filing Date	December 21, 2001
		First Named Inventor	Stringer, Andrew M.
		Group Art Unit	2151
		Examiner Name	Unknown
Total Number of Items in This Submission	5	Attorney Docket Number	717901.20

ENCLOSURES (check all that apply)

<input type="checkbox"/> Fee Transmittal Form <input type="checkbox"/> Fee Attached <input type="checkbox"/> Amendment / Reply <input type="checkbox"/> After Final <input type="checkbox"/> Affidavits/declaration(s) <input type="checkbox"/> Extension of Time Request <input type="checkbox"/> Express Abandonment Request <input type="checkbox"/> Information Disclosure Statement <input checked="" type="checkbox"/> Certified Copy of Priority Document(s) <input type="checkbox"/> Response to Missing Parts/ Incomplete Application <input type="checkbox"/> Response to Missing Parts under 37 CFR 1.52 or 1.53	<input type="checkbox"/> Drawing(s) <input type="checkbox"/> Licensing-related Papers <input type="checkbox"/> Petition <input type="checkbox"/> Petition to Convert to a Provisional Application <input type="checkbox"/> Power of Attorney, Revocation Change of Correspondence Address <input type="checkbox"/> Terminal Disclaimer <input type="checkbox"/> Request for Refund <input type="checkbox"/> CD, Number of CD(s) _____	<input type="checkbox"/> After Allowance Communication to a Technology Center (TC) <input type="checkbox"/> Appeal Communication to Board of Appeals and Interferences <input type="checkbox"/> Appeal Communication to TC (Appeal Notice, Brief, Reply Brief) <input type="checkbox"/> Proprietary Information <input type="checkbox"/> Status Letter <input checked="" type="checkbox"/> Other Enclosure(s) (please identify below) Priority Claim; return postcard.
Remarks:		

RECEIVED

APR 11 2003

Technology Center 2100

SIGNATURE OF APPLICANT, ATTORNEY, OR AGENT

Firm or Individual Name	Kevin M. Kercher, Reg. No. 33,408 Blackwell Sanders Peper Martin LLP
Signature	<i>[Handwritten Signature]</i>
Date	Apr 11, 2003

CERTIFICATE OF TRANSMISSION/EXPRESS MAILING

I hereby certify that this correspondence is being facsimile transmitted to the USPTO or deposited with the United States Postal Service with sufficient postage as Express Mail in an envelope addressed to: Commissioner for Patents, Washington, DC 20231 on this date: April 9, 2003. Express Mail Label No.: EV202549250US			
Typed or printed name	Beth Hookway		
Signature	<i>Beth Hookway</i>	Date	4/9/03

This collection of information is required by 37 CFR 1.5. This information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you are required to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.

If you need assistance in completing the form, call 1-800-PTO-9199 (1-800-786-9199) and select option 2.



#12
Turner B
PATENT 717901.20
7/04

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of: Andrew Mark Stringer)
)
U. S. Patent Application Serial Number: 10/039,565)
)
U.S. Filing Date: December 21, 2001)
)
PCT No.: PCT/GB00/02413)
)
)
)
)
)
International Filing Date: June 21, 2000)
)
Priority Data:)
U.K. Patent No. 9914418.0)
Filed June 22, 1999)
)
For: COMPUTER NETWORK)
PAYMENT SYSTEM)
)
Attorney Docket: 717901.20)

Examiner: Unknown.

Group Art Unit: 2152

Customer No.: 27,128

Confirmation No.: 3948

RECEIVED
APR 11 2003
Technology Center 2100

**PREVIOUSLY MADE PRIORITY CLAIM UNDER 35 U.S.C. § 119 BY THE FILING OF
CERTIFIED COPIES OF PRIORITY PATENT APPLICATIONS**

Applicant is hereby submitting certified copies of PCT Application No.
PCT/GB00/02413 that was filed 21 June 2000 and Great Britain Patent Application No.
9914418.0 that was filed 22 June 1999. This perfects the previously made claim to priority.

If you have any questions or comments, please do not hesitate to contact the undersigned
attorney listed below.

Respectfully submitted,

Date: April 9, 2003

Kevin M. Kercher

Kevin M. Kercher

Reg. No. 33,408

Blackwell Sanders Peper Martin LLP

720 Olive Street, 24th Floor

St. Louis, Missouri 63101

(314) 345-6000

ATTORNEY(S) FOR APPLICANT

WORLD INTELLECTUAL PROPERTY
ORGANIZATION

世界知识产权组织

ORGANIZACION MUNDIAL
DE LA PROPIEDAD INTELECTUAL



10 | 03585
ORGANISATION MONDIALE
DE LA PROPRIÉTÉ INTELLECTUELLE


المنظمة العالمية للملكية الفكرية #12

ВСЕМИРНАЯ ОРГАНИЗАЦИЯ
ИНТЕЛЛЕКТУАЛЬНОЙ СОБСТВЕННОСТИ

CERTIFICATION

It is hereby certified that the attached copy is a true copy of the record copy of International Application No. PCT/GB00/02413, filed with the United Kingdom Patent Office as receiving Office on 21 June 2000 (21.06.00) and received by the International Bureau on 18 July 2000 (18.07.00), including any pages containing corrections and/or rectifications transmitted by the competent Authority to, and received by, the International Bureau before the completion of the technical preparations for international publication.

By: The International Bureau



Linda Schreyer
Head
PCT Examination Section II

Date: 21 January 2003 (21.01.03)

RECEIVED

APR 1 1 2003

Technology Center 2100

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No. **PCT/GB 00 / 02413**

International Filing Date **21 JUNE 2000**

United Kingdom Patent Office
PCT International Application

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum) **P24003A/HGR/**

Box No. I TITLE OF INVENTION

"Computer Network Payment System"

Box No. II APPLICANT

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

STRINGER Andrew Mark
14 Berkeley Close
Hill Head
Fareham
Hampshire
PO14 3NW
United Kingdom

☒ This person is also inventor.

Telephone No.

RECEIVED

Facsimile No.

APR 11 2003

Teleprinter No.

Technology Center 2100

State (that is, country) of nationality:
United Kingdom

State (that is, country) of residence:
United Kingdom

This person is applicant for the purposes of:



all designated States



all designated States except the United States of America



the United States of America only



the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

☐ applicant only

☐ applicant and inventor

☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of:



all designated States



all designated States except the United States of America



the United States of America only



the States indicated in the Supplemental Box



Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:



agent



common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

Murgitroyd & Company
373 Scotland Street
GLASGOW
G5 8QA
United Kingdom

Telephone No.

0141 307 8400

Facsimile No.

0141 307 8401

Teleprinter No.



Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Box No V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes: at least one must be marked):

Regional Patent

- ☒ **AP** **ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☒ **EA** **Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP** **European Patent:** AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ **OA** **OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line).....

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | | | |
|--|---------------------------------------|--|---|
| <input checked="" type="checkbox"/> AE | United Arab Emirates | <input checked="" type="checkbox"/> LC | Saint Lucia |
| <input checked="" type="checkbox"/> AL | Albania | <input checked="" type="checkbox"/> LK | Sri Lanka |
| <input checked="" type="checkbox"/> DZ | Algeria | <input checked="" type="checkbox"/> LR | Liberia |
| <input checked="" type="checkbox"/> AG | Antigua and Barbuda | <input checked="" type="checkbox"/> LS | Lesotho |
| <input checked="" type="checkbox"/> AM | Armenia | <input checked="" type="checkbox"/> LT | Lithuania |
| <input checked="" type="checkbox"/> AT | Austria | <input checked="" type="checkbox"/> LU | Luxembourg |
| <input checked="" type="checkbox"/> AU | Australia | <input checked="" type="checkbox"/> LV | Latvia |
| <input checked="" type="checkbox"/> AZ | Azerbaijan | <input checked="" type="checkbox"/> MA | Morocco |
| <input checked="" type="checkbox"/> BA | Bosnia and Herzegovina | <input checked="" type="checkbox"/> MD | Republic of Moldova |
| <input checked="" type="checkbox"/> BB | Barbados | <input checked="" type="checkbox"/> MG | Madagascar |
| <input checked="" type="checkbox"/> BG | Bulgaria | <input checked="" type="checkbox"/> MK | The former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BR | Brazil | <input checked="" type="checkbox"/> MN | Mongolia |
| <input checked="" type="checkbox"/> BY | Belarus | <input checked="" type="checkbox"/> MW | Malawi |
| <input checked="" type="checkbox"/> CA | Canada | <input checked="" type="checkbox"/> MX | Mexico |
| <input checked="" type="checkbox"/> CH and LI | Switzerland and Liechtenstein | <input checked="" type="checkbox"/> NO | Norway |
| <input checked="" type="checkbox"/> CN | China | <input checked="" type="checkbox"/> NZ | New Zealand |
| <input checked="" type="checkbox"/> CR | Costa Rica | <input checked="" type="checkbox"/> PL | Poland |
| <input checked="" type="checkbox"/> CU | Cuba | <input checked="" type="checkbox"/> PT | Portugal |
| <input checked="" type="checkbox"/> CZ | Czech Republic | <input checked="" type="checkbox"/> RO | Romania |
| <input checked="" type="checkbox"/> DE | Germany | <input checked="" type="checkbox"/> RU | Russian Federation |
| <input checked="" type="checkbox"/> DK | Denmark | <input checked="" type="checkbox"/> SD | Sudan |
| <input checked="" type="checkbox"/> DM | Dominica | <input checked="" type="checkbox"/> SE | Sweden |
| <input checked="" type="checkbox"/> EE | Estonia | <input checked="" type="checkbox"/> SG | Singapore |
| <input checked="" type="checkbox"/> ES | Spain | <input checked="" type="checkbox"/> SI | Slovenia |
| <input checked="" type="checkbox"/> FI | Finland | <input checked="" type="checkbox"/> SK | Slovakia |
| <input checked="" type="checkbox"/> GB | United Kingdom | <input checked="" type="checkbox"/> SL | Sierra Leone |
| <input checked="" type="checkbox"/> GD | Grenada | <input checked="" type="checkbox"/> TJ | Tajikistan |
| <input checked="" type="checkbox"/> GE | Georgia | <input checked="" type="checkbox"/> TM | Turkmenistan |
| <input checked="" type="checkbox"/> GH | Ghana | <input checked="" type="checkbox"/> TR | Turkey |
| <input checked="" type="checkbox"/> GM | Gambia | <input checked="" type="checkbox"/> TT | Trinidad and Tobago |
| <input checked="" type="checkbox"/> HR | Croatia | <input checked="" type="checkbox"/> TZ | United Republic of Tanzania |
| <input checked="" type="checkbox"/> HU | Hungary | <input checked="" type="checkbox"/> UA | Ukraine |
| <input checked="" type="checkbox"/> ID | Indonesia | <input checked="" type="checkbox"/> UG | Uganda |
| <input checked="" type="checkbox"/> IL | Israel | <input checked="" type="checkbox"/> US | United States of America |
| <input checked="" type="checkbox"/> IN | India | <input checked="" type="checkbox"/> UZ | Uzbekistan |
| <input checked="" type="checkbox"/> IS | Iceland | <input checked="" type="checkbox"/> VN | Viet Nam |
| <input checked="" type="checkbox"/> JP | Japan | <input checked="" type="checkbox"/> YU | Yugoslavia |
| <input checked="" type="checkbox"/> KE | Kenya | <input checked="" type="checkbox"/> ZA | South Africa |
| <input checked="" type="checkbox"/> KG | Kyrgyzstan | <input checked="" type="checkbox"/> ZW | Zimbabwe |
| <input checked="" type="checkbox"/> KP | Democratic People's Republic of Korea | Check-boxes reserved for designating States (for the purposes of a national patent) which have become party to the PCT after issuance of this sheet: | |
| <input checked="" type="checkbox"/> KR | Republic of Korea | <input checked="" type="checkbox"/> MZ | Mozambique |
| <input checked="" type="checkbox"/> KZ | Kazakhstan | <input checked="" type="checkbox"/> BZ | Belize |

In addition to the designations made above, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except the designation(s) of _____

The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit).

Box No. VI PRIORITY CLAIM		<input type="checkbox"/> Further priority claims are indicated in the Supplemental Box.		
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application: * regional Office	international application: receiving Office
item (1) 22.06.99 22 June 1999	9914418.0	United Kingdom		
item (2)				
item (3)				

☒ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s): **1**

* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.

Box No. VII INTERNATIONAL SEARCHING AUTHORITY			
Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used): ISA /		Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority): Date (day/month/year) Number Country (or regional Office)	

Box No. VIII CHECK LIST; LANGUAGE OF FILING	
This international application contains the following number of sheets: request : 3 description (excluding sequence listing part) : 30 claims : 5 abstract : 1 drawings : 2 sequence listing part of description : 0 Total number of sheets : 41	This international application is accompanied by the item(s) marked below: 1. <input checked="" type="checkbox"/> fee calculation sheet 2. <input type="checkbox"/> separate signed power of attorney 3. <input type="checkbox"/> copy of general power of attorney; reference number, if any: 4. <input type="checkbox"/> statement explaining lack of signature 5. <input type="checkbox"/> priority document(s) identified in Box No. VI as item(s): 6. <input type="checkbox"/> translation of international application into (language): 7. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material 8. <input type="checkbox"/> nucleotide and/or amino acid sequence listing in computer readable form 9. <input checked="" type="checkbox"/> other (specify): Patents Form 23/77
Figure of the drawings which should accompany the abstract: 3	Language of filing of the international application: English

Box No. IX SIGNATURE OF APPLICANT OR AGENT	
Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).	
<div style="text-align: center; font-size: 1.5em; font-family: cursive;">Murgitroyd & Co.</div> <div style="text-align: center;"> Murgitroyd & Company Agents for the Applicant </div>	

For receiving Office use only		2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
1. Date of actual receipt of the purported international application:	21 JUNE 2000 21.06.00	
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA /	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid.	

For International Bureau use only	
Date of receipt of the record copy by the International Bureau:	18 JULY 2000 18.07.00

1 **Computer network payment system**

2

3 The invention relates to a system and method for
4 transferring payments corresponding to the supply of
5 information over a computer network. In particular the
6 invention relates to a system and method for
7 transmitting payment information between servers and
8 clients by means of a hardware infrastructure of linked
9 routers and by means of a specially adapted protocol.

10 The protocol used by the system and method of the
11 invention is referred to herein as "Packet Tariff
12 Protocol" or "PTP". It is to be understood that the
13 term PTP when used in the following description should
14 be taken to mean a protocol adapted for use with
15 systems which transfer data in packets between servers
16 and clients, the protocol enabling the transmittal of
17 payment information between the servers and clients.

18

19 It is also to be understood that the term "packet" when
20 used in the following description should be taken to be

1 a generic term, meaning any discrete package or block
2 of data that is described by any particular protocol,
3 as appropriate to any particular communication layer.
4 For the purposes of the following description the term
5 "packet" should therefore include message, segment,
6 datagram, frame and any other term which by definition
7 or common usage is accepted as meaning a discrete
8 package or block of data in the context of a specific
9 protocol, as appropriate to any particular
10 communication layer.

11

12 Access to the Internet is freely available everywhere
13 and the advent of e-commerce, or electronic trading, is
14 set to revolutionize the way that business is done.
15 However there remains a requirement for effective
16 trading of information itself. As the infrastructure
17 and available bandwidth expand to appropriate levels,
18 the world will become a single, on-line, global,
19 multimedia library. All public domain information will
20 be available to anyone with a network connection, via a
21 simple, easy to use interface, analogous to today's
22 Web browser application. In addition, suitable tools
23 will be developed to manage the information and tailor
24 all that is available to suit the particular needs of
25 each individual. There are two major consequences of
26 this, as follows.

27

28 Firstly, holding information locally will become
29 redundant. This means that books, CDs, prerecorded
30 videotapes and so on will eventually not be required.
31 When information is sufficiently cheap and reaches the
32 necessary levels of specificity and availability, there

1 will be no point in individuals holding local copies of
2 the information, in the form of books, CDs, tapes etc.,
3 that will quickly go out of date. They will simply
4 access the latest, updated information from its
5 original source or retrieve other data (noting that any
6 digital multimedia information is fundamentally just
7 data) from on-line archives.

8
9 Secondly, broadcast media will also become redundant.
10 Radio stations, TV channels, newspapers and journals
11 will no longer serve any purpose. Once again, highly
12 sophisticated information management tools will
13 retrieve information from the massive range of
14 disparate original sources that will come into
15 existence, with the output collated, rationalized and
16 customized to match the particular requirements of each
17 networked individual.

18
19 These changes lie in the future, but are inevitable,
20 and are likely to result in commercial upheaval and
21 colossal social changes. At present, however, there
22 remains a pressing need for a consistent and
23 appropriate system or method to permit the
24 implementation of this trade in information. The
25 system must conform to, and operate under, the
26 conditions that exist within free-market commercial and
27 national economies. It is the development of a
28 proposed solution to this problem which is addressed by
29 the present invention.

30
31 The PTP or "Packet Tariff Protocol" is an element
32 within an effective system for digital networks at

1 packet level. The protocol is envisaged as, but not
 2 limited to, an evolution of the existing TCP/IP
 3 (Transmission Control Protocol/Internet Protocol)
 4 standard that forms the core of the Internet as it
 5 presently exists. However PTP is not limited to TCP/IP
 6 applications, but can be used in any environment where
 7 there is transfer of data in distinct pieces or
 8 packets, for example WAP (Wireless Application
 9 Protocol), UMTS (Universal Mobile Telecommunications
 10 System), GPRS (General Packet Radio Service) or others.

11
 12 According to a first aspect of the present invention
 13 there is provided a method of electronic payment for
 14 data transferred across a computer network containing
 15 at least one client, at least one server and at least
 16 one router which forwards data, the method comprising
 17 the steps of:

18 sending an electronic data request from a client
 19 to a server via one or more routers; and

20 sending electronic data from said server to said
 21 client via one or more routers in response to said
 22 electronic data request, said electronic data having
 23 associated with it a data field containing a value
 24 which represents the commercial value of the data
 25 contained within the electronic data.

26
 27 Preferably the electronic data is transmitted in the
 28 form of packets. Preferably each of said one or more
 29 routers receives an incoming data packet, reads the
 30 value in the data field associated with the incoming
 31 data packet, calculates a new value based on the read
 32 value and the cost of forwarding the data packet, and

1 forwards the data packet with the new value in the
2 associated data field.

3

4 Preferably each of said one or more routers checks
5 whether the value in the data field associated with the
6 incoming data packet falls within predefined parameters
7 and rejects the packet if the value falls outside the
8 predefined parameters. The parameters may depend on
9 the source of the data packet or the originator of the
10 data request.

11

12 The electronic data request may also have associated
13 with it a data field containing a value which
14 represents the commercial value of the data contained
15 within the electronic data request.

16

17 Preferably total accumulated values for transactions
18 between routers or between routers and servers/clients
19 are recorded. These total values may be used as the
20 basis for payments between the operators and/or users
21 of the routers, servers or clients. Periodic clearance
22 payments may be made between the operators and/or users
23 of the routers, servers or clients, the clearance
24 payments corresponding to the total accumulated values.

25

26 According to a second aspect of the present invention
27 there is provided a system of electronic payment for
28 data based on a hardware infrastructure of linked
29 routers, data providers and data users, comprising:

30 at least one client;

31 at least one server for providing electronic data
32 in the form of data packets in response to a request

1 from a client and having its operation governed by a
2 server protocol which causes each data packet sent by
3 the server to have associated with it a data field
4 representing the value of the data contained within the
5 packet;

6 at least one router linked by a hardware
7 infrastructure to said server and said client and
8 having its operation governed by a routing table and a
9 router protocol;

10 whereby the router protocol causes each router to
11 add commercial value to the packet by forwarding it in
12 accordance with the routing table and to update the
13 value contained in the data field within the packet to
14 reflect this added commercial value.

15

16 Preferably the router protocol also includes procedures
17 for rejecting individual packets in accordance with
18 pre-defined parameters related to the value of each
19 packet on receipt.

20

21 According to a third aspect of the invention there is
22 provided a method of electronic payment for data
23 transferred across a computer network containing at
24 least one client, at least one server and at least one
25 part of the network which forwards data, the method
26 comprising the steps of:

27 sending an electronic data request from a client
28 to a server via the part of the network; and

29 sending electronic data from said server to said
30 client via the part of the network in response to said
31 electronic data request, said electronic data having
32 associated with it a data field containing a value

1 which represents the commercial value of the data
2 contained within the electronic data.

3

4 Preferably the electronic data is transmitted in the
5 form of packets. Preferably the part of the network
6 has an associated data processor which reads the value
7 in the data field associated with an incoming data
8 packet received by the part of the network, calculates
9 a new value based on the read value and the cost of
10 forwarding the data packet, and forwards the data
11 packet with the new value in the associated data field.

12

13 The data processor may check whether the value in the
14 data field associated with the incoming data packet
15 falls within predefined parameters and rejects the
16 packet if the value falls outside the predefined
17 parameters.

18

19 According to a fourth aspect of the invention there is
20 provided a method of electronic payment for requested
21 data transferred across a computer network containing
22 at least one client, at least one server and at least
23 one router which forwards data, in which the requested
24 data is sent from said server to said client in the
25 form of a packet,

26 wherein said packet comprises a packet header and
27 packet data,

28 the packet data containing the requested data, and

29 the packet header containing one or more address
30 fields containing address information relating to the
31 client and/or server and a data field containing a

1 value which represents the commercial value of the
2 requested data contained within the packet data.

3

4 Preferably the data is sent via the router which reads
5 the value in the data field of the incoming data packet
6 received by the router, calculates a new value based on
7 the read value and the cost of forwarding the data
8 packet, writes the new value to the data field, and
9 forwards the data packet with the new value in the data
10 field.

11

12 The invention will now be described, by way of example
13 only, with reference to the accompanying figures,
14 where:

15

16 Fig. 1 is a schematic representation of a typical
17 generic form of a digital data packet under the system
18 of the invention;

19

20 Fig. 2 is a schematic representation of a fragment of a
21 network; and

22

23 Fig. 3 is a flow chart showing the operation of a
24 network router under the system according to the
25 invention.

26

27 The invention can best be understood by considering the
28 metaphor of the supply chain with associated added
29 value at each stage. In other words, at each step in
30 the process to supply the information, value is added
31 over and above the intrinsic value of the information.
32 Therefore, an additional cost is associated with the

1 information at each stage, until it reaches its
2 ultimate destination. In practice, this is achieved by
3 the incorporation of a "value" field into each data
4 packet, allied with network protocol extensions to
5 implement and utilize this field in the packet. This
6 is applied in a way that ultimately results in the cost
7 of providing the intrinsic information and the cost of
8 providing the transport service being enumerated and
9 accrued in the value field. These costs are thus
10 accounted for within the same system that actually
11 provides the data transport service, so that the supply
12 chain and the value chain are both incorporated into
13 the network protocols.

14
15 The value field may be augmented with a "priority"
16 field, along the lines that have already been proposed
17 by other bodies as part of existing technical
18 specifications. Within this framework though, the
19 priority field can additionally be used as part of the
20 commercial system if required, so that different
21 services can incur different costs although they may
22 share the same hardware and network infrastructure. In
23 some prior art developments, the "priority" field of a
24 data packet has evolved to serve a more advanced
25 purpose, and the field contains a code that indicates
26 how data should be handled, according to its
27 characteristics. For example, transmission of data
28 that is part of a video stream might not be re-tried if
29 it fails first time, since a degraded video output is
30 considered to be more useful to the ultimate end-user
31 than a pause to wait for all the information to achieve
32 perfect reproduction. In contrast, a file transfer can

1 usually wait for the availability of network capacity,
2 but must ultimately be one hundred percent complete,
3 accurate and checked if it is to be of practical use.

4

5 In the system according to the invention, data is
6 transferred between servers and clients in packets.
7 Fig. 1 shows the typical generic form of a digital data
8 packet under the implementation of PTP.

9

10 The packet 10 is simply data in a mutually understood
11 format. In the example of Fig. 1, it is divided into
12 three sections 1, 2, 3. Each section may be further
13 divided into multiple fields, as described below. The
14 packet header 1 contains general fields 4 for
15 addressing information or other information and also
16 contains a value field 5. The number of general fields
17 4 depends on the protocol used, and it is to be
18 understood that the number of general fields 4 and the
19 position of the value field 5 within the packet header
20 1 may vary. The packet data 2 contains the data 8 and
21 follows the packet header 1. The packet tail 3 follows
22 the packet data 2 and is optional, but would typically
23 contain a field 6 containing the checksum for the
24 packet, or similar error detection information, and may
25 contain other general fields 7. Again it is to be
26 understood that the number of general fields 7 and the
27 position of the checksum field 6 within the packet tail
28 3 may vary. It is to be understood that the value
29 field may be in any position within the packet, for
30 example within the payload or packet data 2, or within
31 the packet tail 3.

32

1 Each data packet 10 includes a value field 5, which
2 contains information about the intrinsic value of the
3 data 8 contained within the packet, and which
4 accumulates the charges made for each step in the
5 provision of the service for supplying that data packet
6 to its ultimate recipient. As an example, this
7 aggregated overall worth may be measured in Network
8 Credit Units (NCU's).

9
10 For the purpose of applying tariffs, the network system
11 is considered to consist of "servers", "routers" and
12 "clients" although in practice a single machine or even
13 a single software application may fulfil more than one
14 of these functions at different times. For example, a
15 router can be considered to be acting as a client to
16 many servers and as a server to many clients, as
17 defined by the routing tables to which it adheres at
18 any particular moment in time.

19
20 Fig. 2 is a diagram showing a network fragment. Under
21 the system of the invention it may operate in the
22 following manner. The web client 20 operated by the
23 ultimate end user requests information in the form of a
24 message that passes through router (N) 22 at the
25 internet service provider (ISP) connection and accrues
26 added value as a result of the action of the transport
27 service. The message subsequently passes through a
28 number of intermediate routers (not shown) and finally
29 through router (A) 24 and accrues more added value for
30 the extra transport service. The intermediate routers
31 and routers (A) and (N) form the network infrastructure
32 carrying the data. The message then arrives at the web

1 server 26, which responds by initiating a data stream.
2 The web server 26 is operated by a content provider.
3 The packets of this data stream typically have
4 intrinsic value, associated with the information that
5 they contain, the information being provided or sold by
6 the content provider. The appropriate component of
7 this intrinsic value is recorded in each packet. The
8 packets then pass back via router (A) 24 and have the
9 associated value of the transport service added to
10 them. Similarly, router (N) 22 passes the data stream
11 and adds further value to the packets for the service
12 provided. The information finally arrives at the web
13 client 20, as required.

14
15 For each machine on the network, the net values of
16 packets received and transmitted via each hardware
17 connection can then be calculated. These values are
18 reconciled by the owners of all the machines involved,
19 as the basis for assessing the economic value of the
20 services provided and calculating the commensurate hard
21 currency exchanges required. This process is described
22 in more detail below.

23
24 In accordance with the PTP idea, the web client 20, or
25 any software application functioning as a client,
26 maintains the right to reject individual packets if
27 they are deemed "too expensive" by some criteria,
28 without assuming their associated notional cost.
29 Additional control is maintained by monitoring the
30 value of incoming packets in real time, typically by
31 summing the total value arriving in the last second
32 and/or minute and/or hour and/or other time interval,

1 as required. This might, for example, be depicted by a
 2 meter representation or bar indicator on a network
 3 terminal screen. Over a short time period, of the
 4 order of a few seconds or so, it might be acceptable to
 5 have a large amount of data arriving with a large value
 6 at a high rate of value accrual, for example when
 7 downloading a software application. However over a
 8 longer time period, of the order of an hour or so, a
 9 high rate of value accrual might be unacceptable while
 10 it might be acceptable to have a continuous stream of
 11 data arriving with a smaller value, for example when
 12 downloading a movie or video in real time. A meter
 13 representation could also apply to an Internet
 14 telephone, and the system could show the cost of a call
 15 as it takes place, rather than the owner subscribing to
 16 the service on a predetermined tariff scheme. This
 17 does not preclude a service provider agreeing to absorb
 18 the fluctuations in cost and passing on packets at
 19 agreed rates if such a service is desired by clients on
 20 the network. This might be appropriate, for example,
 21 if a client actually desired predetermined costs for
 22 use of the system, e.g. for budgeting purposes.

23

24 The invention is now described in more detail. For the
 25 purposes of the description herein, a packet originates
 26 from a server that acts as a "content provider", i.e.
 27 it is the source of the data or information contained
 28 within the packet that is to be transferred. This
 29 piece of information and the service of providing it
 30 both have some inherent worth and this worth can be
 31 enumerated and written in the value field of the
 32 packet. This is the first element of the system of the

1 present invention, in that content providers can attach
2 a value to the information that they provide and,
3 further, they can assert the claim to that value along
4 the same delivery channel as that by which the
5 information itself is supplied. On receipt of the
6 packet, the client (or router acting as a client) can
7 accept the packet or reject it. The control system
8 which makes the decision and determines the outcome of
9 this choice is described later. It is of importance,
10 because information cannot meaningfully be returned
11 once received.

12
13 Assuming that a router receives and accepts a packet,
14 it then acts in its role as a server and forwards it in
15 accordance with the routing tables it currently holds.
16 It should be noted that this always entails sending the
17 packet down a physical data connection of some sort.
18 The network is defined by the routing tables, but
19 always has a physical existence as data conduits
20 between machines. In the system of the invention, the
21 routing machine defines the worth associated with the
22 action of passing a packet from one machine to the
23 next. It might be a fixed rate, or it might be
24 dependent on the priority of the packet or on some
25 other parameters (e.g. network loading, time of day,
26 physical distance between machines, available
27 bandwidth, ownership of network infrastructure, etc.).
28 The important point is that this evaluation can be
29 resolved by the router (probably as part of its routing
30 software) as it passes the packet and that the outcome
31 of this calculation is added to the value field of the
32 packet in transition (i.e., before it is forwarded).

1 This is the second element of the system of the present
2 invention, in that network infrastructure providers can
3 attach a value to the service of transporting
4 information and, further, they can assert the claim to
5 that value along the same delivery channel as that by
6 which the information itself is supplied. It is also
7 necessary for each machine to accumulate the total
8 number of NCU's it receives from each physical
9 connection and the total number of NCU's it dispatches
10 to each physical connection, excluding those attributed
11 to packets that are subsequently rejected. It should
12 also be noted that physical connections for the receipt
13 of packets are considered to be distinct from physical
14 connections for the dispatch of packets, even though
15 they might be manifested in the same piece of cabling.

16

17 Under these conditions, the number of NCU's transmitted
18 from the machine at one end of a physical connection
19 should agree with the number of NCU's accepted by the
20 machine at the other end. These machines may be owned
21 by different organizations but, on the basis that they
22 agreed to make the trades, they should be reasonably
23 expected to have mutual interest in ensuring accuracy
24 in accounting. A commercial analogy for this would be
25 a deal done on an "open outcry" trading floor, in which
26 two parties agree a deal by signals and each makes a
27 record of it independently. The independent records
28 are reconciled at a later stage but, since both parties
29 agreed the initial deal, both are assumed to have an
30 interest in making sure that it is recorded accurately.
31 The analogy goes further, since any party that
32 establishes a reputation for not recording deals

1 accurately will simply find it impossible to establish
2 or maintain any profitable trades.

3

4 Within this protocol, any recipient reserves the right
5 to reject any packet. This rejection includes refusal
6 to accept the debt associated with receipt of the
7 packet. The most probable reason for this is that the
8 packet is deemed by some criteria to be "too
9 expensive". This act of rejection is an important part
10 of the protocol and therefore warrants detailed
11 discussion. As discussed above, once data is received
12 it cannot be meaningfully returned, since it is not a
13 physical object. On first inspection, then, it seems
14 that there would be a propensity to defraud suppliers
15 by rejecting packets (and therefore the liability to
16 pay for them) whilst still forwarding the data and
17 charging for it. However, the post-receipt rejection
18 process is vital to remove completely the possibility
19 that single "rogue" packets of massive value are
20 foisted on unsuspecting recipients. The reason that an
21 immediate breakdown of the system according to the
22 invention does not follow is because successful trading
23 requires streams of many packets of modest value to be
24 passed through the network. In the proposed scenario,
25 the "catch 'em once" price-value combination is
26 excluded by this ability to refuse to pay for
27 excessively costly packets. This means that a
28 sustainable and profitable trade will only occur with
29 the transmission of an ongoing packet stream.

30

31 This "reject" aspect of the system according to the
32 invention may best be understood by considering a "sale

1 or return" analogy. A producer (content provider)
2 creates a product (data/information) and delivers it to
3 a reseller (router) at some cost (the value in NCU's).
4 The reseller (router) either accepts it, on the basis
5 that it can be sold on (forwarded to another router or
6 an end client) at a marked up price (an addition to the
7 value in NCU's) or, alternatively, rejects it. The
8 producer (content provider) monitors the rejections of
9 the reseller (router) and decides on the basis of this
10 information whether or not to continue trading and, if
11 so, what price structure to apply. Hence, the choice
12 of acceptance or rejection of a packet is effectively a
13 "sale or return" of the data, since keeping occasional
14 packets without paying for them is of little economic
15 value. In practice, it will rapidly become the case
16 that meaningful trade in packet streams allied to
17 competitive pricing is the only way to maintain
18 profitable transactions.

19

20 Termination criteria are based upon single packet costs
21 and the cost accumulations of packets over selected
22 time intervals. Hence termination requests are issued
23 if any single packet exceeds the NCU threshold or if
24 the limits for NCU's per second, minute, hour, day
25 and/or other time interval are exceeded. The cut-off
26 levels are best kept confidential to avoid prices being
27 bumped up to the maximum that would be accepted,
28 although such information could be shared with trusted
29 counterparts in an attempt to reject packets deemed too
30 costly at an earlier stage. Note that single-packet
31 rejection is the only rejection where packets are not
32 paid for, other termination is simply a request to

1 cease supplying data. Data received before supply
2 terminates are still paid for, subject to single packet
3 criteria.

4
5 Conversely, the value attributed to data by content
6 providers could be freely advertised. This would make
7 competition between content providers more effective
8 and would also highlight expensive transport routes,
9 since the value of the packet received would have had
10 risen unacceptably when compared to the initial value
11 advertised by the content provider. Furthermore, data
12 network routing should become an extremely efficient
13 market because data transmission networks can be
14 reconfigured so easily and pricing structures changed
15 so readily. This should result in perfect competition,
16 evolving to satisfy the laws of supply and demand in a
17 free market.

18
19 The final element of the system according to the
20 invention is achieved by converting the residual
21 difference in NCU's exchanged between a pair of
22 machines over some physical connection into a payment
23 in mutually acceptable hard currency. This can always
24 be achieved bilaterally, but could also be administered
25 by some kind of clearing house with responsibility for
26 a defined physical region of the network. There is a
27 potential problem here, unless the exchange value of an
28 NCU is pegged to some hard currency. Otherwise, it
29 will float erratically as the number of NCU's per
30 network transaction can vary inversely with the
31 exchange rate to hard currency, without changing the
32 actual monetary worth of the network transaction. The

1 problem might however eventually resolve itself if the
2 NCU becomes a stable, global currency in its own right.

3

4 To complete a transaction using this system, an
5 ultimate client could first issue a request for some
6 information. For the purpose of this example only, it
7 will be assumed that this request is contained in a
8 single packet. The intrinsic value of this packet
9 would probably be zero but, in all cases, could not
10 exceed a predetermined maximum accepted by the router
11 (which may well be the machine of a network service
12 provider, acting at this point as a client). Further,
13 since this machine is probably not owned by the owner
14 of the ultimate client machine, there would be no
15 tariff added to the value of the packet. The router,
16 now acting as a server, adds a tariff to the packet and
17 passes it to the next router. This process is repeated
18 across the network until the packet reaches the machine
19 of the content provider that, somewhat confusingly, is
20 at this point acting as a client. Hence, the content
21 provider receives a request for information but becomes
22 liable for the accrued value of the packet. This value
23 will be relatively small, since it is only one packet
24 (or, more generally in practice, a relatively small
25 number of packets) and it has little or no intrinsic
26 value in its information content. It can be thought of
27 as analogous to the cost associated with a free-phone
28 telephone number that businesses commonly use to
29 attract enquiries from customers.

30

31 The machine of the content provider now acts in its
32 primary role as a server, and starts to send packets

1 addressed to the machine of the ultimate client (i.e.
2 the machine from which the original request for data
3 originated). Since the packets have content that is
4 deemed to have some worth, these packets now have a
5 significant value associated with them even as they are
6 dispatched from the server machine. As they traverse
7 the network, they will accrue further value until they
8 reach the ultimate client machine. Routers within the
9 network will have added value to packets passing both
10 ways, so that owners of these machines will be in
11 residual credit after paying for the packets received
12 and will therefore be able to reclaim hard currency
13 converted from NCU's to finance their activities. The
14 content providers will have some liabilities for the
15 receipt of the packets requesting data but will have a
16 large residual credit for supplying the information.
17 The ultimate client will contribute the majority of the
18 payments due, which cover the cost of the information
19 they receive and the cost of the process of
20 transporting it to them.

21
22 The way in which a network router might implement the
23 PTP, in addition to its existing transport protocol,
24 for the purposes of transferring data packets and
25 accumulating the associated tariffs, is illustrated in
26 the flow chart of Fig. 3. The branches in the flow
27 chart show possible contingencies at various stages, if
28 the required conditions are not satisfied.

29
30 The router receives 30 a data packet and checks 32
31 whether the packet is acceptable under the existing
32 transport protocol. The router also checks 32 whether

1 the routing tables with which it is provided can
2 resolve the address to yield the hardware connection
3 along which the packet is to be dispatched. If the
4 packet is acceptable and the address can be resolved
5 the router proceeds to step 36. If the packet is not
6 acceptable or the address cannot be resolved the router
7 rejects 34 the packet.

8

9 The router then checks 36 that the value of the packet
10 as determined from the value field 5 is below the value
11 limit acceptable from the incoming hardware connection.
12 If the value of the packet is not below the value limit
13 the router rejects 38 the packet under the PTP rules.
14 If the value of the packet is below the value limit the
15 router proceeds to the next step, in which the recorded
16 total value received from this hardware connection is
17 incremented 40 by the value of the packet. The
18 recorded total value received is stored by the router.

19

20 The router then calculates 42 the value to be added for
21 the service of transmitting this packet along the
22 particular hardware connection designated by the
23 routing tables. This might depend upon the
24 infrastructure of the hardware connection, the
25 prevailing network loading, the time of day and many
26 other factors. The router then increments 44 the
27 packet's value field 5 which is the packet's internal
28 record of its own value by this calculated value.

29

30 The router then transmits 46 the packet along the
31 hardware connection along which the packet is to be
32 dispatched. Following transmittal the router checks 48

1 that the recipient machine has acknowledged successful
2 transfer of the packet (assuming the transfer protocol
3 supports this). If the transfer is not successful,
4 then this is handled under the existing transport
5 protocol 50. If the transfer is successful the router
6 increments 52 the recorded total value transmitted to
7 this hardware connection by the value of the packet.
8 The recorded total value transmitted is stored by the
9 router.

10

11 For each router or hardware connection, the total value
12 transmitted minus the total value received (e.g. in
13 Network Credit Units) is the net profit (or loss) that
14 must be reconciled with the owner of the machine at the
15 other end of that hardware connection. This is used to
16 determine the economic value of the accumulated
17 transactions and forms the basis of the hard currency
18 exchanges necessary to finance the activities and the
19 provision of the infrastructure.

20

21 Physical network connections can be created and re-
22 arranged relatively easily and network service
23 providers can normally be changed at will. It is
24 therefore anticipated that the kind of business system
25 envisaged by the present invention will lead to a very
26 efficient market constituted of very many providers of
27 connections and routing bandwidth who serve,
28 collectively, a very large number of content providers
29 and information consumers. For example, if the
30 financial arrangements were controlled in this manner,
31 it might reasonably be envisaged that the
32 infrastructure would evolve to support video on demand.

1 This would be based upon an enormous supply of
2 material, effectively a distributed archive of all the
3 material ever produced. It would satisfy the market by
4 the laws of supply and demand.

5
6 One of the major problems associated with any data
7 distribution, and particularly digital data, is that of
8 unauthorized redistribution. Matters of privacy and
9 security are also general problems in the context of
10 the Internet. For the purposes of the description of
11 the invention, it is necessary only to consider whether
12 the use of PTP implies any changes as compared to the
13 situation at present. The system of the invention does
14 not require transfer of data in ways other than those
15 presently possible, and the proposed protocol of the
16 invention would not inhibit any of the security or
17 encryption methods used to prevent such unauthorised
18 redistribution. In fact, security and encryption would
19 be expected to take place at the level of the data
20 within the packet stream, rather than acting at the
21 packet level itself.

22
23 One important feature of the system of the invention is
24 that it allows consumers to choose exactly what they
25 require without having to pay for unwanted accompanying
26 material. For example, they can select one track
27 without having to pay for a complete music CD, or they
28 can decide not to view the remainder of a film if they
29 dislike the opening portion. Also, the purchase price
30 should be subject to very keen competition. These
31 facts in themselves mean that there is less temptation
32 to acquire material from illegal sources. Any legal

1 deterrents become more effective if individuals can buy
2 selectively only what they actually require, and at a
3 fair price.

4
5 In addition, as individuals are presented with, and
6 begin to utilize, the much greater choice of available
7 information, their interests will rapidly diversify and
8 their requirements will diverge. This will have the
9 effect of making it more difficult to cache data as it
10 passes through the network and resell it multiple
11 times. If content becomes sufficiently cheap, it will
12 not be worth the investment in hardware to cache it.
13 There will be less demand for any particular content,
14 so that the logistics of illegal storage for reselling
15 become more expensive and therefore less attractive.
16 This is not to say that a legal business of caching and
17 reselling popular information could not build up, still
18 within this framework. This could, for example, be how
19 what are now broadcast services continue to make money.
20 Network capacity will need a large step-change before
21 commonly required content can be served to all clients
22 from a single source, a matter which is presently
23 addressed by the use of network caches, proxy servers
24 and mirror sites on the Web. Such issues are tied in
25 with copyright and ownership of content. For example,
26 it is not generally possible for an end-user to tell
27 whether content comes from its original provider or
28 from some legitimate or illegitimate cache. Once
29 again, the implementation of the system of the
30 invention would not impact upon these matters of
31 copyright and ownership of content.

32

1 The system of the invention as described above can also
2 function with the concept of the network computer,
3 which for example means that a user might have the
4 option of purchasing the use of a software application
5 for some period rather than actually buying the
6 application outright. Once again, they receive (and
7 pay for) only what they actually require, and always
8 get the most up to date version so that rapid
9 obsolescence is not a concern.

10

11 One other important feature of the PTP concept is that
12 it can be interfaced with a conventional network,
13 operating under a different business model, provided
14 charging rates and so forth are agreed for the
15 interfaces. This means that network fragments can be
16 created or converted to conform to the PTP model as and
17 when suits the infrastructure owner, so that gradual
18 conversion is possible and a massive "roll-out" program
19 is unnecessary.

20

21 It is possible that, for effective operation, the
22 system of the invention will require international
23 financing deals and clearing arrangements, as well as
24 software controlled real-time network configuration
25 changes and real-time pricing structure changes.
26 However, the system of the invention offers two
27 significant advantages, as follows. Firstly, the
28 ultimate client always has transparent data on what the
29 service being received is actually costing, over any
30 desired time interval. This is regardless of the
31 choice of information source, network service or demand
32 driven costing changes. Secondly, PTP represent a good

1 approximation to a perfectly competitive and efficient
2 market, and one in which the costs and revenues are
3 intimately related at all stages to the actual
4 activities from which they result. These features
5 should be expected to encourage serious investment into
6 infrastructure development.

7
8 Particular details of a method of implementing PTP in a
9 TCP/IP environment will now be described. In
10 particular, for the value quantity to be directly
11 accessible for processing by the routers, the value
12 field must be contained in the IP Layer header. This
13 is because the TCP Layer header is considered purely as
14 data by the routers that implement IP protocols and, as
15 such, it is to be transported without any reference to
16 its contents. However, for the value field to be
17 useful to individual client and server applications for
18 the purpose of enumerating the intrinsic worth of the
19 data being transported, it must be accessible to these
20 applications. The applications operate at the
21 Application Layer of the TCP/IP stack and this layer
22 interfaces with the TCP Layer, with the IP Layer being
23 effectively invisible to the application. The matter
24 is further complicated by the existence of UDP (User
25 Datagram Protocol), which provides an alternative
26 protocol at the Transport Layer (and there might be
27 additional alternatives, which either currently exist
28 or will be defined in the future). The invention
29 proposes three solutions to this, as follows.

30

31 The first solution is to have separate value fields.
32 According to this solution there are two distinct value

1 fields, one in the IP Layer, to accrue measurement of
2 the economic worth of performing the data transport
3 operation, and one in the Transport Layer, to enumerate
4 the intrinsic worth of the data. Such a solution does
5 not allow the unification of the methods covering the
6 two contributions to the economic model, and so is not
7 the preferred solution.

8

9 The second solution is direct communication between the
10 application and the IP Layer. Such communication can
11 be hazardous with respect to the structure and
12 implementation of the TCP/IP protocol and is not
13 generally considered to be a realistic solution. There
14 is a useful exception in the case of an "information
15 server", a system dedicated to serving information on
16 behalf of a content provider and which is accessed by a
17 client dedicated to the task of receiving that
18 information. A server in such a system can run
19 customised application software, in which the direct
20 access to the IP Layer is available as required. The
21 client works solely with the incoming information, so
22 that the resources consumed (and measured in accordance
23 with PTP) on behalf of the client application are
24 indistinguishable from the total resources consumed by
25 the client machine. This is the maximum level of
26 detail that could be measured if the PTP values were
27 accessed directly from the IP Layer, since IP does not
28 work with reference to specific ports or the individual
29 applications which are notionally attached to them.

30

31 The third, most favoured solution is integration with
32 the Transport Layer. The PTP value field is

1 incorporated in the IP Layer header. The Transport
2 Layer protocol (TCP, UDP or other) is aware of the
3 value field and can convey the information to and from
4 the Application Layer as required, even though this
5 information is not written in the Transport Layer
6 header and thus not considered to be conveyed at the
7 Transport Layer level. The act of reading and writing
8 the value field would still be expected to be the
9 preserve of the of the IP Layer implementation
10 software. This structuring appears to be analogous to
11 the way in which applications can have access to IP
12 addresses, although these are actually written in to,
13 and read back from, the IP headers.
14

15 Practical details in implementing the router
16 functionality required by the PTP system will now be
17 described. Incrementing the value field does not
18 impose an unacceptable processing overhead on the
19 router. There is a precedent for this kind of
20 processing in the way that the IP standard defines and
21 utilises a time-to-live (TTL) value in the IP header.
22 This is subject to a decrement each time a router hop
23 occurs. This capability can be extended to include a
24 simple addition to the value field at the same point in
25 the processing. This operation is likely to be an
26 integer addition or binary add function on a specific
27 bit field in the packet header, a relatively
28 straightforward procedure. At the same time
29 developments in hardware technology will go some way to
30 compensating for the increased burden placed upon the
31 network infrastructure by the implementation of PTP.
32 Dedicated hardware may be used to support the value

1 field modification. Since there is an intimate
2 relationship between the physical network connections
3 and the particular value of the increment to be
4 applied, an appropriate piece of equipment can be
5 placed "in line" on each physical network connection,
6 to perform the task. Such a unit can respond to its
7 own communications protocol (something akin to the way
8 routers work with ICMP (Internet Control Message
9 Protocol), ARP (Address Resolution Protocol) and RARP
10 (Reverse Address Resolution Protocol)) to receive
11 updates to the algorithm for the value to be added to
12 passing packets and also to return accumulated totals
13 at appropriate times. Otherwise it operates as a
14 standalone piece of network infrastructure, logging and
15 incrementing the values of passing packets. Such a
16 configuration alleviates the need for routers to
17 allocate the accumulating values to particular network
18 connections or IP addresses in real time, as they
19 process the packets.

20

21 In addition, it is also possible that, rather than each
22 and every router performing its own increment to the
23 value field, a more "coarse grained" implementation of
24 the PTP model could be applied. This would occur if
25 the provider of a particular piece of infrastructure
26 were willing to consider that piece of infrastructure
27 (e.g. an optical fibre "backbone") as a zone and
28 therefore apply a more straightforward tariff for
29 transportation across the zone. This would mean that
30 the logging and increasing of the value fields of
31 packets transported across the zone would only need to
32 take place at the zone boundaries. This scheme is

1 effectively equivalent to considering the flow chart of
2 Fig. 3 to apply to a network zone rather than an
3 individual router.

4

5 These and other modifications and improvements can be
6 incorporated without departing from the scope of the
7 invention.

1 **CLAIMS**

2

3 1. A method of electronic payment for data
4 transferred across a computer network containing at
5 least one client, at least one server and at least one
6 router which forwards data, the method comprising the
7 steps of:

8 sending an electronic data request from a client
9 to a server via one or more routers; and

10 sending electronic data from said server to said
11 client via one or more routers in response to said
12 electronic data request, said electronic data having
13 associated with it a data field containing a value
14 which represents the commercial value of the data
15 contained within the electronic data.

16

17 2. A method according to Claim 1 in which the
18 electronic data is transmitted in the form of packets.

19

20 3. A method according to Claim 2, wherein each of
21 said one or more routers receives an incoming data
22 packet, reads the value in the data field associated
23 with the incoming data packet, calculates a new value
24 based on the read value and the cost of forwarding the
25 data packet, and forwards the data packet with the new
26 value in the associated data field.

27

28 4. A method according to Claim 3, wherein each of
29 said one or more routers checks whether the value in
30 the data field associated with the incoming data packet
31 falls within predefined parameters and rejects the

1 packet if the value falls outside the predefined
2 parameters.

3

4 5. A method according to any preceding Claim, wherein
5 the electronic data request has associated with it a
6 data field containing a value which represents the
7 commercial value of the data contained within the
8 electronic data request.

9

10 6. A method according to any preceding Claim, wherein
11 total accumulated values for transactions between
12 routers or between routers and servers/clients are
13 recorded.

14

15 7. A method according to Claim 6, wherein clearance
16 payments are made between the operators and/or users of
17 the routers and servers/clients, the clearance payments
18 corresponding to the total accumulated values.

19

20 8. A system of electronic payment for data based on a
21 hardware infrastructure of linked routers, data
22 providers and data users, comprising:

23 at least one client;

24 at least one server for providing electronic data
25 in the form of data packets in response to a request
26 from a client and having its operation governed by a
27 server protocol which causes each data packet sent by
28 the server to have associated with it a data field
29 representing the value of the data contained within the
30 packet;

31 at least one router linked by a hardware
32 infrastructure to said server and said client and

1 having its operation governed by a routing table and a
2 router protocol;

3 whereby the router protocol causes each router to
4 add commercial value to the packet by forwarding it in
5 accordance with the routing table and to update the
6 value contained in the data field within the packet to
7 reflect this added commercial value.

8

9 9. A system according to Claim 8, wherein the router
10 protocol also includes procedures for rejecting
11 individual packets in accordance with pre-defined
12 parameters related to the value of each packet on
13 receipt.

14

15 10. A method of electronic payment for data
16 transferred across a computer network containing at
17 least one client, at least one server and at least one
18 part of the network which forwards data, the method
19 comprising the steps of:

20 sending an electronic data request from a client
21 to a server via the part of the network; and

22 sending electronic data from said server to said
23 client via the part of the network in response to said
24 electronic data request, said electronic data having
25 associated with it a data field containing a value
26 which represents the commercial value of the data
27 contained within the electronic data.

28

29 11. A method according to Claim 10 in which the
30 electronic data is transmitted in the form of packets.

31

1 12. A method according to Claim 11, wherein the part
2 of the network has an associated data processor which
3 reads the value in the data field associated with an
4 incoming data packet received by the part of the
5 network, calculates a new value based on the read value
6 and the cost of forwarding the data packet, and
7 forwards the data packet with the new value in the
8 associated data field.

9
10 13. A method according to Claim 12, wherein the data
11 processor checks whether the value in the data field
12 associated with the incoming data packet falls within
13 predefined parameters and rejects the packet if the
14 value falls outside the predefined parameters.

15
16 14. A method of electronic payment for requested data
17 transferred across a computer network containing at
18 least one client, at least one server and at least one
19 router which forwards data, in which the requested data
20 is sent from said server to said client in the form of
21 a packet,

22 wherein said packet comprises a packet header and
23 packet data,

24 the packet data containing the requested data, and
25 the packet header containing one or more address
26 fields containing address information relating to the
27 client and/or server and a data field containing a
28 value which represents the commercial value of the
29 requested data contained within the packet data.

30

31 15. A method according to Claim 14, wherein the data
32 is sent via the router which reads the value in the

1 data field of the incoming data packet received by the
2 router, calculates a new value based on the read value
3 and the cost of forwarding the data packet, writes the
4 new value to the data field, and forwards the data
5 packet with the new value in the data field.

1 **ABSTRACT**

2

3 A method of electronic payment for data transferred
4 across a computer network from a server (26) to a
5 client (20) by means of at least one router (22, 24)
6 which forwards data. An electronic data request is
7 sent from the client to the server via one or more
8 routers. The server (26) then sends electronic data
9 (8) to the client (20) via one or more routers in
10 response to said electronic data request. The
11 electronic data is sent via a packet transfer protocol,
12 in which each packet of data (10) has associated with
13 it a data field (5) containing a value which represents
14 the commercial value of the requested data (8). Each
15 router (22, 24) receives an incoming data packet (10),
16 reads the value in the data field (5) associated with
17 the incoming data packet, calculates a new value based
18 on the read value and the cost of forwarding the data
19 packet, and forwards the data packet (10) with the new
20 value in the associated data field (5). Each router
21 can check whether the value in the data field (5)
22 associated with the incoming data packet falls within
23 predefined parameters and rejects the packet if the
24 value falls outside the predefined parameters, for
25 example if the value of the data is too high. Each
26 router stores the accumulated value of received and
27 forwarded data, so that payments may be made to the
28 operator of the router.

1 / 2




Fig. 1




Fig. 2

2 / 2




Fig. 3




FIG. 1





FIG. 2

REPLACED

2/2

FIG. 3

REPLACED